

Mac-Weld Integral Meter Run Assembly

Brand: Mac-Weld



Short Description

Supplied fully assembled and ready for installation Available with flanges, threads or weld bevel connections Designed for line sizes up to 12" Meter runs above 12" available upon request Suitable for steam, gas and liquid flow measurement Large selection of materials available NACE compliant CRN's available upon request, see factory for details Dye Pen, X-Ray and Hydro testing available

Description

Mac-Weld meter run assemblies are designed as a complete unit allowing for easy installation, while also improving overall reliability. Meter runs are commonly manufactured to standard lengths; however, they can be designed for custom applications, which will help achieve optimal efficiency at the transmitter. Mac-Weld meter run assemblies are delivered as a single unit, which includes flange union, orifice plate & either flanged, threaded or weld bevel connections. We can also pre-install manifolds and transmitters when requested (transmitters supplied by client).